## **Triangle Universities Nuclear Laboratory**


# Precision Measurements of $\gamma$ -Ray Attenuation Coefficients at HI $\gamma$ S



Henry R. Weller, M. Ahmed, C. Moss, C. Frankle, V. Litvinenko

#### **Motivation**

- The need of the SBSS program to quantitatively measure density profiles from radiographs using high–energy flash x–ray machine (PHERMEX);
- Present errors on total absorption cross–sections are  $\sim 2-3$  %, which is too large when propagated through the transmission equation. Goal here is to reduce these errors to < 0.5 %. An accuracy of  $\sim 0.2$  % has been achieved (see Table below).




Schematic of the storage ring and FEL used to produce the gamma-ray beams

#### **HIGS Performance**

## **Current**; **Booster Injector** (~late 2005)

Energy 2-50 MeV 2-225 MeVFlux  $\gamma/\text{sec}$   $10^5-10^8$   $10^8-10^9$ Polarization Linear Linear & Circular

Measurements have been performed on Be, C, Ta, W, Pb, depleted U. More samples, especially actinides, need to be measured. Support is needed to enable HIGS/Duke University to handle special nuclear materials.



Setup for  $\gamma$ -ray attenuation measurements.


### **HIGS Measurement**

 E(MeV)
 σ(b) HIGS
 σ(b) NIST

 5.98 +/- 0.04
 3.255+/- 0.007
 3.28

## **Future**

Additional measurements of differential cross–section as a function of angle are needed. A scoping experiment designed to look at the feasibility of this is in the planning stage.



a) HIGS spectrum at 6 MeV, no sample; b) Cu sample two attenuation lengths thick.